



Australian Government

Australian Nuclear Science & Technology Organisation

# **Cost Estimation, Funding for both HIFAR – MOATA Research Reactors**

**Presented by John Rowling  
Manager / Facilities Management**



Australian Government

**Ansto**

# **INTRODUCTION**

- **Strategy & Approach**
- **Cost calculations**
- **Funding arrangement**
  - **Focusing of “TRANSITION”**

**There were 5 other reactors of similar design, UK (3), Denmark and Germany**



Australian Government

**Ansto**

# **Strategy and Approach**

## **How to make up the costings?**

**Labour team for the total project (Time & Cost)**

**Particular Projects**

**Map the Stages**

**List the Activities**

**Special Equipment requirements**

**Contingency**

**Neglect the cost savings (May not happen)**

**When?**

**Where is the origin of the funding?**

**Why – Justification?**


**What is the process?**



Australian Government



# Closure and Decommissioning Plan





Australian Government

**Ansto**

# **HIFAR Decommissioning Team**

## **Project Manager**

- **Planner**
- **2 Engineers**
- **2 Contractor Engineers**
- **2 Operators (1 Trainer)**
- **Active Handling Supervisor**
- **4 Active Handlers (Labouring)**
- **1 QA & Document person**
- **2 Health Physics Surveyors**
- **2 Maintenance Staff (Mechanical & Electrical p/t)**

**Team of 20 staff**



Australian Government

**Ansto**

# **Major Decommissioning Projects**


- **Electrical Distribution Board**
- **Active Ventilation & HVAC Systems**
- **Security & Access System**
- **Communication System**
- **Lighting System**
- **Fire Alarm System**
- **Radiation Instrumentation**
- **Monitoring System**



Australian Government

Ansto

# HIFAR Shell (Non nuclear)



- Strip out all electrical & Instrumentation wiring
- Strip out all light water pipework
- Install AC
- Remove SCS & ductwork
- Removal all non-active material

FIGURE 1.1-2 REACTOR STRUCTURE

# HIFAR Shell (Nuclear)





FIGURE 1.1-2 REACTOR STRUCTURE

- Strip out all Helium circuit pipework (02 cct)
- Strip out all small heavy water pipework (01 cct)
- Removal all pumps
- Maintain Active extract system
- Maintain Crane
- Cover top plate and storage block



# DIDO / UK





Australian Government

**Ansto**

## **Transitioning**

- **Closure Team (20 people)**
- **Budget of \$10 Mio AUD (est)**
- **Term (2 years) 2007 & 8**

## **Decommissioning 2014+**

- **Budget of \$40 Mio AUD (est)**
- **Decommissioning Team (20 people)**



Australian Government

**Ansto**

## **Data To Other Similar Reactors**

**UKAEA £23 million (act) (AUD \$57Mio)**

**Denmark DnK300million (est) (AUD \$50Mio)**

# Dismantling Plan & Estimates

## Phase 1: Preparation

Duration: **9 months (50% effort)**

Cost: **\$900K + 10% contingency**

### Procedures:

- Prepare project plans & procedures
- Procure resources, contractors, etc.
- Survey radiation (non-destructive)
- Update characterisation
- Update radioactive inventory lists
- Prepare Env. Impact Studies (EIS)
- Obtain approval (the EPBC Act)
- Revise project cost estimate
- Prepare submissions (SAC, etc.)
- Obtain ARPANSA approval

## Phase 2: Dismantling ([Ref 4.1.2](#))

Duration: **3 months (100% effort)**

Cost: **\$2,000K + 10% contingency**

### Procedures:

- Survey radiation (core sampling)
- Establish boundary of active zones
- Set up temporary containment
- Set up active ventilation & control
- Remove detachable components
- Remove metal core components
- Remove fuel storage pits
- Drill 80 holes into non-active zone
- Fill holes with 'expanding grout'
- Control dust with recycled water
- Jack-hammer non-active zones
- Contain & demolish active zone
- Segregate waste into LLW & ILW
- Truck Free-Release waste to the tip
- Contain and seal LLW and ILW

## Phase 3: Post Dismantling

Duration: **6 months (50% effort)**

Cost: **\$900K+ 10% contingency**

### Procedures:

- Carry out final surveys
- Validate 'greenfield' status
- Make good the site
- Hand over active waste for storage
- Submit for de-licensing
- Hand over the site: unrestricted use
- Complete documentation
- Review and close the project

# ARGONAUT Reactors

Reactor	Power	Dismantled	Contractor	Cost (Approx.)
Virginia P, USA	100 kW	1988		US\$0.6M
UCLA R1, USA	100 kW	1992	NES Inc.*	US\$1.7M
THAR, Taiwan	10 kW	1993		US\$0.5M
The Universities Research Reactor, Risley, UK	300 kW	1996	BNFL	£4M comprising; •£2M (dismantling) •£1M (waste) •£1M (fuel removal)
JASON Reactor*, Greenwich, UK	10 kW	6/1999 Visited by S. Kim, ANSTO [Ref 4.1.3]	AEA Tech.*	£7M comprising; •£2M (management) •£2M (dismantling) •£1M (waste) •£2M (fuel removal)
University of Washington*, USA	100 kW	Delayed	NES Inc.*	US\$1.7M ('94 value) plus US\$0.5M for decontaminating spills
Iowa State University*, USA	10 kW	8/2000 Observed & assisted by S. Kim, [Ref 4.1.2]	Duke Eng. & Services*	US\$1M comprising; •US\$0.2M – Planning •US\$0.6M – Dismantling •US\$0.2M – Final survey
<b>Moata</b>	100 kW	Proposed 2008/9		<i>Estimated (See ER111484)</i> (a)ANSTO: <b>\$3.8M+</b> (b)DES: US\$2M+** (c)NES: US\$3M+** (d)AEA Tech.: £5M



Australian Government

**Ansto**

# **Project Planning (1 of 2)**

- **Breakdown the work into stages or phases**
- **Breakdown the stages into activities**

## **1.1 Pre-decommissioning Stage**

### **1.2 Decommissioning Planning**

### **1.3 Authorisation**

- **Licensing**
- **SAR**

## **2.1 Shutdown Stage**

- **Plant Shutdown**
- **Fuel Removal**
- **Heavy Water Drainage**



Australian Government

**Ansto**

# **Project Planning (2 of 2)**

## **3.1 Project Stage**

### **4.1 Dismantling Stage**

### **4.2 Decontamination of Equipment**

### **5.1 Safe Enclosure Stage**

- Demolition of Associated Buildings
- Removal of unnecessary Structures

### **6.1 Decommissioning Stage**

### **6.2 Dismantling of operating Equipment**

- Primary & secondary circuits
- Redundant Pumps and Pipework

### **6.3 Dismantling of Reactor Block & Building**



Australian Government

**Ansto**

# WASTE VOLUMES

Description of Item / Building / Facility / Equipment / Plant	Estimated Value of D & R Incl. Transport of Waste (Items 1 to 8)	Estimated weight	Estimated Volume	Cost/m3	Estimated Cost of Disposal charges only	Expected Date of D & R	Notes
	\$	tonne	m <sup>3</sup>		\$		
<b><u>Nuclear</u></b>							
- HIFAR and ancillary Buildings	\$ 50,180,000	1000	500	\$ 4,000	\$ 2,000,000	2007 to 2020	Three stage decommissioning process to a greenfield site.
- Moata	\$ 5,805,093	60	120	\$ 4,000	\$ 480,000	2012	Decommissioning costs based on US experience for similar reactor.





Australian Government

**Ansto**

# Questions?



RCB Before Painting, 24/4/01 [Pic#3]



Australian Government

**Ansto**



Australian Government

**Ansto**