#### **Profile LFR-79**

## **LECOTH**

## **CHINA**

GFN	IFKAL	INFOR	MATION

NAME OF THE FACILITY Lead-bismuth Eutectic COmprehensive THermal-hydraulic test facility

ACRONYM LECOTH

MEDIUM (COOLANT(S)) OF LBE

THE FACILITY

LOCATION (address): CNPRI, Shenzhen, China

OPERATOR CNPRI CONTACT PERSON(S) Jiming Lin

(name, address, institute, China Nuclear Power Technology Research Institute (CNPRI)

function, telephone, email): 0086-755-88617716

linjiming@cgnpc.com.cn

STATUS OF THE FACILITY Under Design

Start of operation (date): 2020

MAIN RESEARCH FIELD(S) ☐ Zero power facility for V&V and licensing purposes

☐ Design Basis Accidents (DBA) and Design Extended Conditions

(DEC)

☐ Coolant chemistry

☐ Materials

oxtimes Systems and components

☐ Instrumentation & ISI&R

## **TECHNICAL DESCRIPTION**

## Description of the facility

LECOTH is a forced-convection loop for exposing industrial grade oxygen control experiment and thermal fluid mechanics experiment of fuel assemble to flowing LBE at temperatures between 280 °C and 550 °C. The facility is designed for tests in LBE having a flow up to 50m³/h and can provide about 0.5Mpa pressure for the experimental section.

## Acceptance of radioactive material

No

Click here to enter text.

## Scheme/diagram




FIG.1. Scheme of the COTHELA facility

# 3D drawing/photo

# NO

# Parameters table

Medium (Coolant) inventory	1000L	
Power	2500KW	
Test sections		
	<u>Characteristic dimensions</u>	
TS #1	1500mm length. 1000mm diameter	
	Static/dynamic experiment	
	dynamic	
	Temperature range in the test section (Delta T)	
	280℃-550℃ (270℃)	
	Operating pressure and design pressure	
	atmospheric	
	Flow range (mass, velocity, etc.)	
	30m³/h, 2m/s	
TS #2	<u>Characteristic dimensions</u>	
13#4	61 samples, 3015mm height, 150mm width	

	Static/dynamic experiment	
	dynamic	
	Temperature range in the test section (Delta T)	
	220°C-450°C (230°C)	
	Operating pressure and design pressure	
	0.44MPa	
	Flow range (mass, velocity, etc.)	
	31m³ /h, 2m/s	
Medium (Coolant)	Active oxygen control system by Pt/air, Bi/Bi <sub>2</sub> O <sub>3</sub> oxygen sensors and gas	
chemistry	phase oxygen exchanger.	
measurement and	Active fuel assemble system by pressure sensors and flow sensors	
control		
(active or not,		
measured		
parameters)		
Instrumentation	Flow meter	
	Oxygen sensors	
	Temperature sensors	
	Pressure sensors	

# COMPLETED EXPERIMENTAL CAMPAIGNS: MAIN RESULTS AND ACHIEVEMENTS

No

# PLANNED EXPERIMENTS (including time schedule)

Industrial-scale oxygen control experiments (from 2020-07-01 to 2020-12-31)

Thermodynamic experiment of fuel assembly (from 2021-01-01 to 2021-11-30)

## TRAINING ACTIVITIES

Training activities are possible, depending on availability and after prior agreement under supervision of CNPRI

# REFERENCES (specification of availability and language)

No